



~~GEORGE K. BURNHAM, JR.~~
~~EST. 1918~~

3439 PLEASANT PLACE . BALTIMORE 11, MD.
P.O. Box No. 4799

FORMERLY WILLIAMS ENG. CORP.

March 23, 1965

Mr. J.E. Myers
7728 Wynbrook Road
Baltimore, Maryland 21224

Sub: United Evangelical Church

Gentlemen:

We propose to point masonry, caulk exterior openings and apply two coats of silicone to the North and East walls of above mentioned subject for the sum of ----- ONE THOUSAND SIX HUNDRED EIGHTY DOLLARS (\$ 1,680.00). If we are to do the South wall of court, add the sum of FOUR HUNDRED EIGHTY DOLLARS ----- (\$ 480.00).

Very truly yours,

Burnham Engineering Co., Inc.

George F. Wisner
George F. Wisner, Estimator

Lincoln Tile and Linoleum Company

700 SOUTH ELLWOOD AVENUE

Baltimore 24, Md.

Asphalt, Linoleum, Rubber, Plastic and Cork Tile

A FLOOR FOR EVERY TYPE BUSINESS OR HOME

FREE ESTIMATES

United Evangelical Lutheran Church
East Avenue and Dillion Street,
Baltimore 24, Maryland.

March 11 1965

Gentlemen:

I am submitting the following contract for work to be done at the above location. Removing all the shoe molding and laying 1/8 inch thick 9 by 9 Armstrong Vinyl Asbestos tile, and nailing the shoe molding on.

All work to be first class and guaranteed for one year from the day of completion.

Total labor and material \$2,500.00

Respectfully submitted Walter J. Wasik.

Walter J. Wasik

H. N. REDMER

Painters and Decorators

1730 INGRAM ROAD, BALTIMORE, MARYLAND 21214

IDLEWOOD 5-0924

March 8, 1965

United Evangelical Church
East Avenue & Dillon Street
Baltimore 24, Maryland

Gentlemen;

I, the contractor, propose and agree to do the following interior and exterior painting of your property located at the above address, furnishing all material, tools, labor and equipment necessary for this work, for the amounts quoted:

INTERIOR:

Ceilings and walls to be pointed-up where necessary, sanded smooth and to receive one or two coats of paint, as required for a first class job, ceilings of rooms receiving acoustic tile not to be painted.

Woodwork and trim to be sanded smooth, puttied and to receive one coat of enamel undercoater and one coat of enamel.

Third floor _____	\$520.00
Second floor _____	\$815.00
First floor _____	\$745.00
Front stairway _____	\$410.00
Rear stairway and Men's Room(2 coats) _____	\$655.00

EXTERIOR:

Woodwork and trim of entire educational building to be sanded smooth, puttied and to receive two coats of exterior paint.

All loose paint and putty shall be removed and windows be reputtied. -----\$545.00

Colors to be selected by the owner.

Insurance : Workmen's Compensation and Public Liability to be carried by the contractor.

CONTRACT ACCEPTED:

Respectfully,

H. N. Redmer

Baltimore 30, Md., March 7 19 65

Estimate for job at school
located at East Ave + Willow St.
Baltimore, Md.

R. C. O'BROCKI
ELECTRICAL CONTRACTOR

LICENSED AND BONDED
BALTIMORE CITY
1274 Battery Ave.

TERMS: Net Cash - Bills Due when rendered

Labor and material as stated
on construction sheet,
(excluding lighting fixtures)
four (4) new interiors and breakers
in stairwells and permit

\$ 2,485.00

You will have to purchase
22- 8 ft. 2 tube fixtures
21- 4 ft. 2 tube fixtures

NO RECEIPT UNLESS REQUESTED

NICHOLAS AUMILLER & SON

WATER HEATERS • PLUMBING • HEATING

Repairs - - - Service

3100 E. MONUMENT ST. BALTIMORE 5, MD.

Broadway 6-5785 - Day or Nite



Baltimore 5, Maryland
March 2, 1965

United Evangelical Church
c/o Mr. Edward Meyers
7728 Wynbrook Rd.
Baltimore 24, Md.

Dear Sirs,

In referance to the work to be done in the school building we propose the following:

To Install

4^{1/2} Wall hung electric water coolers. \$864.00

1- Model LKR 520 Combination sink, range and refrigerator installed. \$487.00

Change 4" cleanout in gym. \$35.00

Install

2- Rest rooms on 3rd. floor consisting of (3) closet combinations (2) basins and (1) urnal. \$1750.00

Vent 1- Rest room to outside with an electric blower fan. \$90.00

No electric work, tile or painting has been figured in this price.

The above material and labor will be installed in first class manner of grade A material and workmanship.

We

We thank you for this opportunity to quote and hope to have the pleasure of serving you.

Yours truly

Nicholas Aumiller Jr.



THE PAUL-RICE ENGINEERING CO.

Mechanical Contractors

2000 VINE STREET

BALTIMORE 23, MD.

PROPOSAL

SUBJECT: School Building - Revised Heating

March 1, 1965

TO:

Mr. Edwin Myers
7728 Wynbrook Road
Baltimore, Maryland 21224

Gentlemen:

We are pleased to quote you the sum of FIVE THOUSAND, ONE HUNDRED FORTY THREE DOLLARS (\$5,143.00) to revise the heating system in your three story school building. We have included all necessary labor, material, tools and equipment for a complete job as follows:

After inspecting the school building we found the boiler was adequate to heat the building, however, the heat was not being distributed properly. We have not figured to do any work on the boiler or increase the size of the boiler.

We have added the following heating units:

Third floor - 11 convectors
Second floor - 6 convectors
First floor - 4 convectors
Ground floor - 2 unit heaters

If the above is acceptable we will furnish you with sketches of each floor showing location of the new units and where we propose to tie into the existing piping.

VERY TRULY YOURS,

THE PAUL-RICE ENGINEERING CO.

BY:


Larry San Boeuf

LSB/avh



JOHN H. HAMPSHIRE, INC.

Over 50 Years of Dependable Service



HOME OFFICE 330 WEST 24TH ST. • BALTIMORE, MARYLAND 21211

Branch Offices WASHINGTON OFFICE
4626 ANNAPOLIS ROAD
BLADENSBURG, MD. 20710

RICHMOND OFFICE
2513 CHAMBERLAYNE AVE.
RICHMOND, VA. 23222

ROANOKE OFFICE
2101 WINSTON AVE., S.W.
ROANOKE, VA. 24014

NORFOLK OFFICE
714 FRONT STREET
NORFOLK, VA. 23510

CHARLESTON OFFICE
1112 KANAWHA TERRACE
ST. ALBANS, W. VA. 25177

March 30, 1965

REPLY TO Home Office

Mr. Ed Schwartz
903 S. Conklin Street
Baltimore, Maryland 21224

Re: Movable Partition
United Evangelical Church

Dear Mr. Schwartz:

To furnish all labor and material necessary to complete the installation of Neslo Movable Partition, approximately 42 lineal feet long and 9' 5" high with unfinished steel trim and gypsum board and one unpainted standard door buck (no door) we quote the sum of SEVEN HUNDRED DOLLARS.....\$700.00. If aluminum trim and vinyl covered gypsum board (unpainted standard door buck) is desired, add \$250.00 to this price.

To give you some idea of what it would cost to paint the unfinished partition so that you would have a comparative cost, I consulted our partition manager, Win Hurley, who used to work for Pittsburgh Paint Company (P.P.G.). He said that \$135.00 was a reasonable figure. Therefore, it would cost your congregation about \$115.00 to have the aluminum and vinyl partition. This would certainly be a worthwhile investment.

If I can be of any further assistance to you in this matter, please call me at your convenience.

Very truly yours,

JOHN H. HAMPSHIRE, INC.

Brian D. McCarthy
Brian D. McCarthy

BDMc:dh

The Stebbing Company

ACOUSTICAL TREATMENT AND SOUNDING CONDITIONING

1600 CLOUGH STREET — BALTIMORE 13, MD.

April 1, 1965

Mr. E. Myers
7728 Wynbrook Road
Baltimore, Maryland 21224

Re: United Evangelical Church
Acoustical Ceilings

Gentlemen:

This quotation is for the installation of Armstrong Mylar Minaboard 24" x 48" x 5/8" thick, nominal size on the Eastern Product exposed grid system suspended from the structure above. All labor to be performed during regular working hours.

3rd Floor - East	\$990.00
3rd Floor - West	590.00
2nd Floor - East	605.00
2nd Floor Office	125.00
2nd Floor Hall	200.00
Audio-Visical	130.00
Boy Scouts	310.00
	<u>\$2,950.00</u>

The Second floor - east room includes either a bulkhead or a splay at the window wall to return the ceiling up over the window head.

Very truly yours,

THE STEBBING COMPANY

Richard D. Carson
Richard D. Carson

RDC:Emd

W. M. Schoenfelder & Associates, Inc.

ARCHITECTURAL PRODUCTS

~~4017 ST. ELMO AVENUE~~

~~PO BOX OFFICE BOX 8020~~

~~BETHESDA 14, MARYLAND~~

~~OLIVER 4-8560~~

W. M. SCHOENFELDER
PRESIDENT

RICHARD I. SCHOENFELDER
VICE PRESIDENT

April 5, 1965

JAMES M. GREEN
BALTIMORE OFFICE
330 E. 28TH STREET
BALTIMORE 18, MD.
AREA CODE: 301-243-8853

Mr. John E. Myers
7728 Wynbrook Rd.
Baltimore, Md. 21224

RE: United Evan. Church
East Ave. & Dillon St.
Baltimore, Md. 21224

ATTEN.: Mr. J.E. Myers

SUB: FOLDING PARTITIONS

Gentlemen:

We are pleased to quote the following prices for Hufcor sound insulated accordian partitions as manufactured by the Hough Mfg. Corp. of Janesville, Wisconsin. We are quoting on a 41'-6" wide opening to open in the center, permanently attached at one wall and detachable at the other. When making reference to 8'-0" high partitions, it will be necessary for a bulk head to be dropped down from the ceiling to receive the track. When making reference to ceiling height partitions, all our prices are based on heavy duty extruded aluminum track with factory painted double wide flange sub-channel. This sub-channel will be furnished to the job to be installed by the ceiling contractor on a firm wood support furnished by them.

PRICE # 1: Series 2500, 8'-0" high, class 22, nine hundred eleven dollars (\$911.00).

PRICE # 2: Series 3500, 8'-0" high, class 38, one thousand, one hundred forty-two dollars (\$1,142.00).

PRICE # 3: Series 2500, ceiling height, class 22, one thousand, two hundred fifty-six dollars (\$1,256.00).

PRICE # 4: Series 3500, ceiling height, class 38, one thousand, five hundred seventy dollars (\$1,570.00).

PRICE # 5: Series 4500, ceiling height, class 42, one thousand, eight hundred six dollars (\$1,806.00).

PRICE # 6: In the event you should desire a cremone bolt to be installed six feet (6'-0") from the interior wall which will permit a short section of the partition to be operated as a pass through, add the sum of forty-five dollars (\$45.00), to any of the above prices.

All of the above prices include installation of the partitions. We do not include the bulk head for the 8'-0"

PAGE - 2 -

Continuation of letter for quotations on folding partitions.

partitions or the wood grounds for the ceiling height partitions, as we are of the opinion that this work could most economically be performed by the ceiling contractor. If this does not prove to be satisfactory, please contact us for further pricing.

Please contact us as soon as possible regarding the outcome of the above quotations.

Very sincerely yours,

W. M. SCHOENFELDER & ASSOC., INC.

A handwritten signature in cursive script that reads "James M. Green".

James M. Green, Mgr.
Baltimore Office

JMG:bm

The Stebbing Company

ACOUSTICAL TREATMENT AND SOUNDING CONDITIONING

1600 CLOUGH STREET — BALTIMORE 13, MD.

April 5, 1965

Mr. E. Meyers
7728 Wynbrook Road
Baltimore, Maryland 21224

Re: United Evangelical Church
Movable Partition and
Plaster Patching

Gentlemen:

We propose to furnish all necessary labor, material and equipment for the installation of Pennwall movable partition with one opening on the 3rd floor east of the above reference job for \$350.00. Partition to be approximately 42' x 9'6" with 1/2" Gypsum Board Finish and ready for paint. The door frame, door, painting and base shall be furnished and installed by others. Also the plaster patching throughout the building as explained by Mr. Swartz complete and ready for paint for the sum of \$300.00.

Very truly yours,

THE STEBBING COMPANY

Blake C. Pruner

Blake C. Pruner

BCP:lmd

CHARLES INGRAM & COMPANY
MANUFACTURERS REPRESENTATIVES
TUXEDO 9-2443

2437 N. CALVERT ST.

April 6, 1965

BALTIMORE, MD. 21218

Mr. J. E. Meyers
 7728 Wynbrook Rd.
 Baltimore, Md. 21224

Sub: Folding Fabric Doors
 United Evangelical Church

Gentlemen:

Confirming our recent telephone conversation, we can quote you \$2,500.00 for furnishing and installing one pair of Holcomb & Hoke's Super Sound Guard L-24 for one opening approximate 41'3" long by 10'3" high, description of which can be found on Page 3, in the attached Holcomb & Hoke Catalogue. If Holcomb & Hoke's Souper Sound Guard L--8 be required, discription of which can be found on Page 7, our price would be \$2,000.00.

The above prices do not include the furnishing and installing of necessary blocking to which we attach our channel and track. We quote these prices as a matter of information and we cannot accept an order because of the difficulty in getting the crates of doors to the 3rd floor. This is a major problem as the weight of the L-24 is 6.2 Lbs. per Sq. Ft. and the weight of the L-8 is 3.7 Lbs. per Sq. Ft. Even if the L--8 is used the weight of one crate would be approximately 300 Lbs., which is still to much to take up the steps. If you would permit the use of 4 doors instead of a pair, we would discuss this matter further with our installation men to see if they could handle this weight.

Awaiting your reply, and thanking your for the opportunity of quoting you, we are,

Very truly yours,

CHARLES INGRAM & COMPANY

H. V. Rumsey
 H. V. Rumsey

HVR:elkh
 Encl.

BUILDING SPECIALTIES

PORCELAIN ENAMEL - X-RAY PROTECTION - FOLDING FABRIC DOORS - CHALKBOARDS
 CORK - ROOF DECK - SPECTRA-GLAZE